
# Edge-Spread Functions Expected for Several Changes in a Commercial Flat-Panel System

A.E. Schach von Wittenau

February 25, 2002



Approved for public release; further dissemination unlimited

# DISCLAIMER

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.

This work was performed under the auspices of the U. S. Department of Energy by the University of California, Lawrence Livermore National Laboratory under Contract No. W-7405-Eng-48.

This report has been reproduced directly from the best available copy.

Available electronically at <a href="http://www.doc.gov/bridge">http://www.doc.gov/bridge</a>

Available for a processing fee to U.S. Department of Energy
And its contractors in paper from
U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62

Oak Ridge, TN 37831-0062 Telephone: (865) 576-8401 Facsimile: (865) 576-5728 E-mail: reports@adonis.osti.gov

Available for the sale to the public from U.S. Department of Commerce National Technical Information Service 5285 Port Royal Road Springfield, VA 22161 Telephone: (800) 553-6847 Facsimile: (703) 605-6900

E-mail: <u>orders@ntis.fedworld.gov</u>
Online ordering: <u>http://www.ntis.gov/ordering.htm</u>

OR

Lawrence Livermore National Laboratory
Technical Information Department's Digital Library
http://www.llnl.gov/tid/Library.html

# Edge-spread functions expected for several changes in a commercial flat-panel system

A. E. Schach von Wittenau

Lawrence Livermore National Laboratory, Livermore, CA 94550

(February 25, 2002)

### **SUMMARY**

The Bldg. 239 radiography facility uses a 9 MeV bremsstrahlung linac and a commercially available flat-panel detector system. Ref. [1] discusses the facility in detail. Ref. [1] furthermore discusses the imaging quality of the flat-panel system, and identifies several sources of image blur for the system in question. The major contributors to the imaging blur are radiation scattered from the front cover of the detector housing, radiation scattered from the back cover of the detector housing, and radiation scattered from the aluminum plate that supports the amorphous-Si detector within the detector housing.

The manufacturer of one such flat-panel system seems willing to modify one of their products as requested, if such modifications may be made easily. Easy modifications would include making the detector housing thinner, decreasing the sizes of air gaps inside the detector system, etc. Removing the aluminum support plate is considered to be a difficult modification.

This memo reports the results of a set of Monte Carlo simulations that were performed to predict the changes in imaging quality, compared to that of the current system, if the detector is modified as suggested above. In particular, the edge-spread function (ESF) was calculated for each modification. ESFs were calculated for three photon energies: 100 keV, 450 keV, and 3 MeV.

The results suggest that thinning and moving the front and back covers of the detector housing should result in improved image quality for all of the photon energies considered. Interestingly, the results also suggest that removing the aluminum support plate would improve the imaging performance at 100 keV and 450 keV, but that removing the plate has no additional benefit for imaging with 3 MeV photons.

### I. METHODS AND MATERIALS

The Monte Carlo simulations were performed using MCNP4C. Dimensions and materials specifications were obtained from the manufacturers of flat panel systems. An MCNP input deck for the current imaging system had already been generated for use in Ref. [1]. Changes to the original deck to reflect the changes discussed here required very little effort.

Six detector configurations were modeled, using the methods described in Ref. [1], and the resulting ESFs are shown in Figs. 1–3. The configurations, along with the mnemonics, are:

- 1. none: the original configuration;
- movefront: the front cover has been moved 4 mm closer to the Lanex screen, thus decreasing the air gap between the front cover and the rest of the system;
- 3. **thinfront:** the front cover is thinned to 0.75 mm, but the air gap has the same thickness;
- 4. **thinback:** both the aluminum support plate and the back aluminum plate have half their original thickness; the air gap remains unchanged;

- 5. both: the front cover is moved in, and the two aluminum plates have their thicknesses halved;
- 6. **support:** the front cover is moved in, the back plate is thinned, and the aluminum support plate is removed.

Table 2 of Ref. [1] gives a detailed description of the detector system. An abbreviated description of the structural parameters is given in Table I.

Edge-spread functions were calculated for three photon energies: 100 keV, 450 keV, and 3 MeV. Results are shown in Figs. 1–3.

## II. RESULTS

Fig. 1, for 100 keV photons, shows that all of the changes considered should improve the edge-spread function of the detector. In order of increasing improvement in image quality, the configurations are: none, then movefront, then thinfront, then thinback, then both, then support. This ordering suggests that the front cover is a small contributor to image blur, at this photon energy. Removing the aluminum support plate should have a significant effect on the sharpness of the ESF.

Fig. 2, for 450 keV photons, also shows that all of the changes considered should improve the edge-spread function of the detector. In order of increasing improvement in image quality, the configurations are: none, then movefront, then thinfront, then thinback, then both, then support. This ordering suggests that the front cover is a small contributor to image blur, at this photon energy. The back plates have a significant influence on the image quality, more so than for the 100 keV case. Here, too, removing the aluminum support plate should have a significant effect on the sharpness of the ESF.

The 3 MeV case shows a different pattern. In order of increasing improvement in image quality, the configurations are: none, then thinfront or thinback, then movefront, then support, then both. In this case, adjusting the front cover has a stronger effect than does adjusting the back aluminum plates. This is likely due to the front cover's now being a significant source of scattered radiation. This scattered radiation would be in a forward-directed cone. Moving the front cover closer to the detector element would decrease the projected area of this cone, thus yielding a narrower ESF. Modifying the down-

stream portions of the detector system appears to be less useful.

### ACKNOWLEDGMENTS

This work was performed under the auspices of the U.S. Department of Energy by the University of California, Lawrence Livermore National Laboratory under Contract W-7405-Eng-48.

[1] A. E. Schach von Wittenau, C. M. Logan, M. B. Aufderheide, III, and D. M. Slone, "Blurring artifacts in megavoltage radiography with a flat-panel imaging system: Comparison of Monte Carlo simulations with measurements," submitted to Med. Phys. (2001), UCRL-JC-144247.

TABLE I. Materials, densities, and layer thicknesses used for the MCNP simulations of the notional imaging system.

	Component thickness (mm)						
Component	density	original	${f movefront}$	thinfront	thinback	both	support
Carbon fiber front cover	1.6	1.5	1.5	0.75	1.5	1.5	1.5
air gap	0.0012	6.5	2.5	6.5	6.5	2.5	2.5
Lanex / glass / plastic							_
Al support plate	2.7	4.83	4.83	4.83	2.415	2.415	0.0
air gap	0.0012	20.3	20.3	20.3	20.3	20.3	22.715
Al back cover	2.68	2.54	2.54	2.54	1.27	1.27	1.27




FIG. 1. Edge spread functions for the various cases, assuming a 100 keV monoenergetic beam.




FIG. 2. Edge spread functions for the various cases, assuming a 450 keV monoenergetic beam.




FIG. 3. Edge spread functions for the various cases, assuming a 3 MeV monoenergetic beam.